



Mobile Office Size:

60' long (add 4' for hitch for overall length of 64')
 60' box length
 12' wide
 8' ceiling height

Interior:

Paneled walls
 Vinyl tile
 Gypsum ceiling

Heating & A/C:

3- 12,000 BTU A/C with heat or
 1- 3 ton wall hung central A/C with 10 KW heat

Electric:

100 amp breaker panel - 220v single phase
 Fluorescent ceiling lights

Exterior:

Steel siding and trim
 Outrigger frame
 Drip rail

Furniture:

Built-in desk with file cabinets
 36"x60" plan table
 Coat closet w/shelf and rod

Windows/Doors:

Horizontal sliding windows
 36"x80" exterior door w/lock
 32"x80" bathroom door
 2- 36"x80" interior door