



**Mobile Office Size:**

16' long (add 4' for hitch for 20 overall length)

16' box length

8' wide

7' ceiling height

Open room with no bath

**Interior Finish:**

Paneled walls

Vinyl tile

Gypsum ceiling

**Heating & A/C:**

12,000 BTU A/C with heat strip

**Electric:**

60 amp breaker panel - 220v single phase

Fluorescent ceiling lights

**Exterior:**

Steel siding and trim

Outrigger frame

Drip rail

**Furniture:**

Built-in desk with file cabinet

36"x60" plan table

**Windows/Doors:**

Horizontal sliding windows

36"x80" exterior door w/lock