



**Mobile Office Size:**

20' long (add 4' for hitch for 24' overall length)  
20' box length  
8' wide  
7' ceiling height  
Open room no bath

**Interior Finish:**

Paneled walls  
Vinyl tile  
Gypsum ceiling

**Heating & A/C:**

12,000 BTU A/C with heat strip

**Electric:**

60 amp breaker panel - 220v single phase  
Fluorescent ceiling lights

**Exterior:**

steel siding and trim  
Outrigger frame  
Drip rail

**Furniture:**

Built-in desk with file cabinet  
36"x60" plan table

**Windows/Doors:**

Horizontal sliding windows  
36"x80" exterior door w/lock