



Mobile Office Size:  
 32' long (add 4' for hitch for overall length of 36")  
 32' box length  
 8' wide  
 7' ceiling height  
 2 offices with 1/2 bath

Interior Finish  
 Paneled walls  
 Vinyl tile  
 Gypsum ceiling

Heating & A/C  
 2- 12,000 BTU A/C with heat strip

Electric  
 100 amp breaker panel - 220v single phase  
 Fluorescent ceiling lights

Exterior  
 Steel siding and trim  
 Outrigger frame  
 Drip rail

Furniture  
 2- Built-in desk with file cabinets  
 36"x60" plan table

Windows/Doors  
 Horizontal sliding windows  
 36"x80" exterior door w/lock  
 26"x80" interior bathroom door  
 2- 36" x 80" interior office doors

